

Ultra-Fast Fully Insulated FASTON* Receptacle Terminals

1. SCOPE

1.1. Content

This specification covers the performance requirements for Ultra-Fast fully insulated FASTON* receptacle terminals. These terminals consist of a FASTON receptacle body enclosed in a fully insulated housing. They mate with FASTON tabs on devices used in home entertainment centers, business machines, copying equipment, computer peripherals, appliances and other commercial equipment

1.2. Qualification

When tests are performed on the subject product line, procedures specified in Figure 1 shall be used. All inspections shall be performed using the applicable inspection plan and product drawing.

2. **APPLICABLE DOCUMENTS**

The following documents form a part of this specification to the extent specified herein. Unless otherwise specified, the latest edition of the document applies. In the event of conflict between the requirements of this specification and the product drawing, the product drawing shall take precedence. In the event of conflict between the requirements of this specification and the referenced documents, this specification shall take precedence.

2.1. TE Connectivity (TE) Documents

- 109-1: General Requirements for Test Specifications
- 109 Series: Test Specifications as indicated in Figure 1
- 114-2123: Application Specification

2.2. Commercial Standards

- CSA C22.2 No 153: Quick-Connect Terminals
- DIN VDE 0627: Connectors and Plug-And-Socket Devices
- UL 310: Quick-Connect Terminals, Standard for

3. REQUIREMENTS

3.1. **Design and Construction**

Product shall be of the design, construction and physical dimensions specified on the applicable product drawing.

3.2. Materials

- Receptacle body: Brass or phosphor bronze, tin plated
- Housing: Nylon type 6/6, UL 94V-2
- Tabs (for test purposes): Brass, temper 2, CDA alloy
- Wire (for test purposes): Complies with UL 310 Paragraph 7, 600 Volt rating



3.3. Ratings

Voltage: 600 volts AC maximum

• Operating Temperature: 105°C maximum

3.4. Performance and Test Description

Product is designed to meet the electrical, mechanical and environmental performance requirements specified in Figure 1.

3.5. Test Requirements and Procedures Summary

Test Description	F	Requireme	ent	Procedure				
Examination of Product.	Meets requir drawing and 2123.			TE Spec 109-1. Visual, dimensional and functional per applicable inspection plan.				
	E	LECTRIC	AL					
Dielectric Withstanding Voltage, Test Condition A.	No breakdow 3400 volts A minute.			UL 310, 600 Volt Rating. Test wired terminals in Number 12 lead shot.				
Dielectric Withstanding Voltage, Test Condition C.	No breakdow of terminal w applied for 1	hen 3000	over at rear volts AC are	UL 310, 600 Volt Rating. Test on flat metal plate. See Figure 4.				
Dielectric Withstanding Voltage, Receptacle, Tab Entry Position.	Terminal Size 250 187 110 No breakdow	Voltag	Applied 1e (volts AC) 1000 1000 600 10ver, 1	TE Spec 109-29-1. Test wired terminals on a flat metal plate. See Figure 5.				
Heating (Temperature Rise).	Wire Size (AWG) 26 24 22 20 18 16 14 12 10 20°C maxim	.110 1 2 2 3 4 5 8 -	(amperes) Others 1 2 3 4 7 10 15 20 24 erature rise.	UL 310. Stabilize at specified current and measure temperature rise.				

Figure 1 (continued)



Test Description	F	Requireme	nt	Procedure			
Heat Cycling (Current Cycling).	Wire Size (AWG)	Current .110	(amperes) Others	UL 310. Subject samples to 500 current			
	26 24 22 20	2 4 4 6	2 4 6 8	cycles of 45 minutes ON and 15 minutes OFF.			
	18 16 14 12	8 10 15 –	14 20 30 40				
	10 65°C maxim Δ Temperatu 500 cycles si on any condi	ire rise be hall not ex	48 rature rise. tween 24 and				
Pull Out (Crimp Tensile). Secureness of Insulation		s are less thdrawal for 70 8 m of the in	inimum) 5 0 6 than orce. See 0 0	UL 310. Apply a direct and gradual pull at a rate of 1 inch per minute, 1 minute hold at specified load. UL 310.			
(Unassembled).	the terminal			Subject unwired terminals to a 3 pound pull between the insulation and terminal for 1 minute.			
Secureness of Insulation (Assembled).	No separatio the terminal		sulation from	UL 310. Subject wired terminals to a 6 pound pull between the insulation and terminal for 1 minute.			
Engagement-Disengagement (Engaging-Separating).	See Figure 2			UL 310. Engage and disengage terminals and tabs 6 times.			
	ENV	'IRONMEI	NTAL				
Heat Age, 136°C.	Meet Dielect Voltage, Tes Secureness (assembled	t Conditior of Insulation	n A; and on	UL 310. Subject terminals to 136°C for 7 days.			
Heat Age/Humidity.	Meet Dielect Voltage, Tes		_	UL 310. Subject unwired terminals to 100°C for 7 days followed by 85% RH at 30°C for 24 hours.			

Figure 1 (end)



Tab Size Terminal (Plain Brass)	Force (pounds)									
		First Insertion	,	Sixth Withdrawal						
	Plating	Individual (max)	Individual (max)	Average (min)	Individual (min)	Average (min)	Individual (min)			
.250		17	17	5	3	4	3			
.205/.187	Tin	15	20	5	3	3	2			
.110	.110		14	3	2	2	1			

Figure 2
Engagement and Disengagement Forces

3.6. Terminal Tests and Sequences

	Test Group (a)											
Test or Examination	1	2	3	4	5	6	7	8	9	10	11	12
	Test Sequence (b)											
Examination of Product	1	1	1	1	1	1	1	1	1	1	1	1
Dielectric Withstanding Voltage, Test Condition A		2	3	3(c)								
Dielectric Withstanding Voltage, Test Condition C					2							
Dielectric Withstanding Voltage, Receptacle, Tab Entry Position						2						
Heating (Temperature Rise)	2											
Heat Cycling (Current Cycling)	3											
Pull Out (Crimp Tensile)		3										
Secureness of Insulation (Unassembled)							2		3			
Secureness of Insulation (Assembled)								2		3	3(c)	
Engagement-Disengagement (Engaging-Separating)												2
Heat Age, 136°C			2							2		
Heat Age/Humidity				2					2		2	

NOTE

- (a) See paragraph 4.1.A.
- (b) Numbers indicate sequence in which tests are performed.
- (c) Uncrimped terminals and wires in test groups 4 and 11 shall be conditioned in the environments indicated. After conditioning, each sample is crimped to the appropriate wire and the electrical or mechanical test is performed.

Figure 3

Rev D 4 of 5



4. QUALITY ASSURANCE PROVISIONS

4.1. Qualification Testing

A. Sample Selection

Terminals and tabs shall be prepared in accordance with applicable Instruction Sheets and shall be selected at random from current production. Test groups 1, 2, 3 and 4 shall each consist of 20 samples of each wire size and terminal type per group. Test groups 5, 6, 7, 8, 9, 10, 11 and 12 shall each consist of 20 samples of each terminal type per group. All samples to be terminated shall be crimped to appropriate tin plated test conductors.

B. Test Sequence

Qualification inspection shall be verified by testing samples as specified in Figure 3.

C. Acceptance

- Requirements put on the test samples, as indicated in the Requirements portion of Figure 1, exist as either the upper or lower statistical tolerance limit (95% confidence, 98% reliability).
 All samples tested in accordance with this specification shall meet the stated tolerance limit.
- Failures attributed to equipment, test setup or operator deficiencies shall not disqualify the product. When product failure occurs, corrective action shall be taken and samples resubmitted for qualification.

4.2. Quality Conformance Inspection

The applicable inspection plan will specify the sampling acceptable quality level to be used. Dimensional and functional requirements shall be in accordance with the applicable product drawing and this specification.

4.3. Certification

This product has been recognized under the Component Recognition Program of Underwriters Laboratories Inc., Electrical File Number E-66717 and certified by Canadian Standards Association File Numbers LR-7189. Also, VDE Testing and Certification Institute, Reference No. 4751_1431_1047.




Figure 4
Metal Plate Test Fixture




Figure 5
Tab, Receptacle Entry Position

单击下面可查看定价,库存,交付和生命周期等信息

>>TE Connectivity(泰科)